

ADDENDA & CORRIGENDUM SLIP NO. 11 to CSR-2010

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
1	79	11.74				Providing and laying in super structure for first storey factory made with vibro-hydraulic compaction machine precast solid block of cement concrete setting in position with cement mortar 1:3 (1 cement:3 course sand) including cost of hosting, centering and shuttering complete as per IS:2185 (Part-1): 2005.	New Item added as per Annexure-X-1 (Basic rate taken as on day of preparation hence ceiling premium will be 0% as on date of issue of this A&C Slip)
2	79	11.75				Providing and laying in super structure for first storey factory made with vibro-hydraulic compaction machine precast Hollow block of cement concrete setting in position with cement mortar 1:3 (1 cement:3 course sand) including cost of hosting, centering and shuttering complete as per IS:2185 (Part-1): 2005.	-do-
3	79	11.76				Providing and laying in super structure for first storey factory made precast solid block of cement concrete 100 mm thick of cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size) including cost of Hoisting setting in position with cement mortar 1:3 (1 cement:3 course sand) cost of centering and shuttering complete as per IS:2185 (Part-1): 2005.	-do-
4	79	11.77				Providing and laying in super structure for first storey factory made with vibro-hydraulic compaction machine precast hollow block of cement concrete 100 mm thick setting in position with cement mortar 1:3 (1 cement:3 course sand) including cost of hosting, centering and shuttering complete as per IS:2185 (Part-1): 2005.	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
5	94	13.77				Preformed fillers for expansion joints in concrete pavement and structures (non-extruding and resilient type) part-3 Polymer Based (CED 13: building construction practices including painting, varnishing and allied finishing) complete as per IS 1838-3 (2011):	-do-
6	94	13.78				<p>Providing & laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations:</p> <p>Applying a slurry coat of neat cement using 2.75 kg/sqm. of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer- in- charge over the RCC slab including adjoining walls upto 300mm height including cleaning the surface before treatment.</p> <p>Laying brick bats with mortar using broken bricks/ brick bats 25mm to 115mm size with 50% of cement mortar 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS: 2645 and approved by Engineer-in-charge over 20mm thick layer of cement mortar of mix 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS :2645 and approved by Engineer.</p>	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
7	127	14.163				Providing and fixing Morwad marble strip 18mm to 20mm thick and 100mm wide in kotah stone flooring over 12.50 mm thick base of cement mortar 1:3 jointed with cement slurry including cost of additional mortar equivalent to the kota stone thickness and colouring pigment to match the colour rubbed and polished to granolithic finish complete in all respects.	-do-
8	127	14.164				White marble tile with light green/ yellowish streaks arranged from Morwad flooring 15mm to 20mm thick of various size over 12.5mm thick cement coarse sand mortar 1:3 laid and jointed with white cement slurry mixed with pigment to match the shade of marble including rubbing and polishing	-do-
9	127	a				Tiles Size 15 cm x 15 cm to 28 cm 28 cm	-do-
10	127	b				Slab Size 30 cm x 30 cm to 45 cm x 60 cm	-do-
11	127	c				Slab Size Above 45cm x 60 cm	-do-
12	127	14.165				White marble tiles with Light Green / Yellowish streaks arranged from Morwad of 18 mm to 20 mm thick in risers of skirting dado, pillars and wall lining including matching the 1:3 and jointed neat cement slurry including the cost of cramps labour for fixing cramps pins and dowels etc. including rubbing and polishing complete in all respect.	-do-
13	127	a				Tiles Size 15 cm x 15 cm to 28 cm 28 cm	-do-
14	127	b				Slab Size 30 cm x 30 cm to 45 cm x 60 cm	-do-
15	127	c				Slab Size Above 45cm x 60 cm	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
16	134	15.79				Providing and fixing chicken mesh on brick work and RCC work junction, made of galvanized low carbon wire, annealed wire of diameter 0.6 to 2.0mm distance between the faces of the hexagon 13 to 50mm complete in all respect.	-do-
17	143	16.70				Providing and applying plaster of paris (ISI marked) punning 6mm thickness over plastered surface to prepare the surface even and smooth complete in all respect as per the directions of Engineer-in-charge.	-do-
18	143	16.71				Providing & applying heritage granual homogeneous wall finishing system from Bakelite Coating & Paints Pvt. Consisting of two component system of dry Granual (25 kg/pack) made of 92% silice partical, coated with fade resistant pigments and 100% acrylic co-polymers bonding agent (5 ltr pack) with the applied thickness of coating being between 0.8 to 1.2mm to be applied in single coat on a cured level smooth plastered, as per the shade combination approved and as per manufacturer specification, including primer on base coat complete in all respects	-do-
19	167	17.67				Providing and fixing 65mm wide and 2 to 3mm thick PVC cover on stair case railing in any shape and size fixed with adhesive compound in all respect as per drawings.	-do-
20	167	17.68				Providing & fixing 4" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
21	167	17.69				Providing & fixing 6" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
22	167	17.7				Providing & fixing 9" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
23	167	17.71				Providing & fixing 12" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
24	167	17.720				Providing & fixing 1'-3" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
25	167	17.730				Providing & fixing 1'-6" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
26	167	17.740				Providing & fixing 2'-0" stainless steel handles ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
27	167	17.750				Providing & fixing 4" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
28	167	17.760				Providing & fixing 6" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
29	167	17.770				Providing & fixing 8" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
30	167	17.78				Providing & fixing 1'-0" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
31	167	17.79				Providing & fixing 1'-6" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
32	167	17.80				Providing & fixing 2'-0" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
33	167	17.81				Providing & fixing 2'-6" stainless steel tower bolts ISI marked on door & window frames complete in all respect as per the directions of Engineer-in-charge.	-do-
34	175	18.41				Rebarring (Chemical Anchors) of 8mm dia bar, hole size 12mm, depth 100mm with 10ml injectable mortar epoxy adhesive (Hybrid urethane methacrylate adhesive) rebarring chemical complete in all respect.	-do-
35	175	18.42				Rebarring (Chemical Anchors) of 10mm dia bar, hole size 14mm, depth 100mm with 10 ml injectable mortar epoxy adhesive (Hybrid urethane methacrylate adhesive) rebarring chemical complete in all respect.	-do-
36	175	18.43				Rebarring (Chemical Anchors) of 12mm dia bar, hole size 16mm, depth 120mm with 14 ml injectable mortar epoxy adhesive (Hybrid urethane methacrylate adhesive) rebarring chemical complete in all respect.	-do-
37	175	18.44				Rebarring (Chemical Anchors) of 16mm dia bar, hole size 20mm, depth 160mm with 24 ml injectable mortar epoxy adhesive (Hybrid urethane methacrylate adhesive) rebarring chemical complete in all respect.	-do-
38	175	18.45				Rebarring (Chemical Anchors) of 20mm dia bar, hole size 25mm, depth 200mm with 47 ml injectable mortar epoxy adhesive (Hybrid urethane methacrylate adhesive) rebarring chemical complete in all respect.	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
39	175	18.46				Rebarring (Chemical Anchors) of 25mm dia bar, hole size 32mm, depth 250mm with 100 ml injectable mortar epoxy adhesive (Hybrid urethane methacrylate adhesive) rebarring chemical complete in all respect.	-do-
40	175	18.47				Supply & Fixing of door frames (Chowkhats) consisting frame fabricated from sheet roll formed out of 1.2mm thick galvanized sheet as per IS:277 (base steel as per IS:513) with zinc of 120gm/sqm & Powder coated with pure Polyster powder upto 50 micrones (as per approved colour) , 3 Nos 100mm butt-hinges 2mm thick, 6 Nos 1.2mm thick CRCA electroplated stiffner, 6 Nos M.S hold fast with split and tail welded to stiffner plate 200mm long, Receiver for aldrop, M.S tie rod 50mm x 25mm to be fixed at bottom finished with powder coated total thickness of coating 0.60mm of approved shade, fixed in position, including the cost of cement concrete for 1:2:4 for fixing lugs complete in all respects as per drawing, design, specification & entire stasfication of Enginner-in-Charge.	-do-
41	175	a				Doors frame of size 80mm x 50mm with 37 mm wide single rebate for 35mm door shutter .	-do-
42	175	b				Doors frame of size 125mm x60mm with 37 mm wide Double rebate for 35mm door shutter.	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
43	175	18.48				Supply & Fixing of Window frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 0.58mm thick galvanized sheet (base steel as per IS : 513) with zinc of 120gm/sqm steel sheet pre coated (as per approved colour) with polyster paint of 12-16 micrones thickness under coat of EPOXY primer & back coated with ALKYD backer of 5-7 micrones total thickness of coating 0.58mm of approved shade, fixed in position by means of PVC & metal hold fastner with PVC cap complete in all respects as per drawing, design, specification & entire stasfication of Enginner-in-Charge.	-do-
44	175	a				Windows Outer frame of size 72mm x55mm and central mullion 72 mm x 50mm with Double rebate.	-do-
45	175	18.49				Supply & Fixing of Window shutter consisting frame fabricated from sheet roll formed out of 0.58mm thick galvanized sheet (base steel as per IS : 513) with zinc of 120gm/sqm steel sheet pre coated (as per approved colour) with polyster paint of 12-16 micrones thickness under coat of EPOXY primer & back coated with ALKYD backer of 5-7 micrones total thickness of coating 0.58mm of approved shade, fixed in position fixed in position by means of screws , complete in all respects as per drawing, design, specification & entire stasfication of Enginner-in-Charge.	-do-

Sr. No	Page No.	Item No.	Col. No.	Line No.	As Existing	To be Amended	Remarks
1	2	3	4	5	6	7	8
46	175	a				Glazed Windows shutter Section 47mm x 20mm (Without Glass)	-do-
47	175	18.50				Wire Mesh Windows shutter Section 40mm x 20mm with S.S wire mesh 32 guage flymesh with 144 holes per square inch	-do-
48	175	18.51				Providing & fixing fixed beeding 12mm x 12mm for fixed glass with ECO fixed gasket (EPDM)	-do-
49	175	18.52				Providing and fixing glazing in door, window, ventilator shutters and partitions etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of Gasket /beading shall be paid as per respective item)	-do-
50	175	i				Float glass panes of 5.5 mm thickness	-do-