BOUNDARY WALL 13½" THICK, 6' HIGH (WITH FOOTPATH)

All dimensions in feet & inches. Not to scale.

NOTES

1. Brick work in cement mortar 1:5.
2. D.P.C. at footpath level.
3. Foundation P.C.C. 1:8:16, 1'-0" thick, 2'-6" wide.
4. Plaster / pointing and coping as per site requirement.
5. Provide expansion joints at about 60'-0" c/c.

