BOUNDARY WALL 13½" THICK, 6' HIGH (TYPICAL SECTION)

All dimensions in feet & inches. Not to scale.

NOTES

1. Brick work in cement mortar 1:5.
2. Stepped footing: six courses of 3" each, widening 2¼" per course (1-1/8" on each side).
3. Foundation P.C.C. 1:8:16, 9" thick, 36" wide.
4. D.P.C. at plinth level (3'-6" above N.S.L. as shown).
5. Wall height 6'-0" above D.P.C. level.

